BRUHATH BENGALURU MAHANAGARA PALIKE,DASARAHALLI ZONE
Office of Executive Engineer
SCHEDULE -B

Name Of Work :Construction of Culvert in Bagalagunte ward no.14

Sl.No	Descrption of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	525.00	140.9	
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications	Cum	56.25	4900	
3	Providing and laying in position plain cement concrete of mix M20 with OPC @ 300kgs, with 20mm and down size graded granite metal coarseaggregates @ 0.69 cum and fine aggregtes @ 0.43 cum, machine mixed, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation, plinth and cills, including cost of materials, labour, HOM of machinery, curing complete as per specifications.	Cum	232.03	5425	
4	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200	Tonne	23.20	72327	
5	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	710.00	69	

Signature of Contractor

Executive Engineer
EXECUTIVE ENGINEER
Dasarahalli Division
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73

Scanned by CamScanner